



*Towards European Licensing of
Small Modular Reactors*

International Summer School on Early-Deployable SMRs

2022

HOW TO DESIGN AN EXPERIMENTAL FACILITY

SIET S.p.A.

Roberta Ferri

*Politecnico di Milano
Lake of Lecco
July 7, 2022*



CONTENT

Need of experimental facilities

Need of an experimental facility in the ELSMOR project

Design of an experimental rig: the ELSMOR facility

Scaling

Mechanical design

Instrumentation and Data Acquisition system

Testing

Data analysis

Code validation

NEED OF EXPERIMENTAL FACILITIES

The design and certification of a new nuclear power plant, be it a SMR, requires the execution of experimental tests for different goals:

- the independent verification of the functionality of systems devoted to the safety of the plant, e.g. DHRS. In this case, Separate Effect Test (SET) facilities are necessary;
- the verification of the behavior of the integral system, e.g. primary loop, secondary loops and also containment. In this case, Integral Test Facilities (ITF) are necessary;
- the validation of system codes, e.g. Relap5, Cathare, etc., on qualified experimental data to perform Reactor system analyses versus postulated accidents devoted to obtain the final reactor certification.

NEED OF AN EXPERIMENTAL FACILITY IN THE ELSMOR PROJECT

The need of an experimental facility in the ELSMOR project has basically three goals:

- Indicate the route on how to perform an experimental campaign to the European Regulator called to certify SMRs in Europe;
- test a passive decay heat removal system, to be potentially installed on the E-SMR, based on a compact plate-type heat exchanger included in a natural circulation loop that rejects heat into a water pool;
- validate different codes in pre-test and post-test analyses.

DESIGN OF AN EXPERIMENTAL RIG: THE ELSMOR FACILITY

The ELSMOR facility is a SET loop devoted to test a PDHR system that includes a plate-type heat exchanger (S-CSG Safety-Compact Steam Generator) installed in a natural circulation loop that rejects heat into a water pool by means of a vertical tube heat exchanger.

The potential use of a plate-type heat exchanger in an integral type SMR has the advantage of high power transfer in an extremely compact configuration. It is the first time this kind of heat exchanger is proposed to be part of a nuclear power plant for civil use, so it may require a wide experimentation before the application for licensing.

In general, the design of a facility starts from a technical specification indicating:

- the goal of testing;
- the scaling factors (elevation, volume, power scale);
- the phenomena of interest to be reproduced and investigated;
- the required characteristics of instrumentation and Data Acquisition System (e.g. accuracy, sampling frequency, etc.);
- the Test Matrix.

Reference reactor E-SMR

Electric power ~170 MW

Thermal Power ~515 MW

2 Loops EHRS

Decay power per loop ~30 MW (decay power ~10% reactor power/2 ~26 MW)

The scaling for the ELSMOR facility mainly focuses on two aspects:

- heat exchanger power and pressure drops;
- loop pressure drops.

Type-plate heat exchanger specification

HX power ~500 kW

HX primary side pressure drops ~12 kPa (at 2.8 kg/s nominal flowrate)

HX secondary side pressure drops ~30 kPa (at 0.4 kg/s nominal flowrate)


Natural circulation loop specified height ~6 m.

ELSMOR facility scaling factors:

Elevation 1:1

Power ~1: 50

ELSMOR FACILITY SIMPLIFIED SCHEME



Total height: ~ 15 m

Power ~ 1 MW

(Plate-type HX power ~ 600 kW)

Primary side P: 15.5 MPa; T: 310 °C

Secondary side P: 10 MPa; T: 315 °C

In-pool HX: 5 tubes, 2-inch diameter,
 ~ 2 m length

Cylindrical water pool:


~ 5 m³ volume,

~ 6 m height,
atmospheric pressure

ELSMOR facility HEAT EXCHANGER

HX Specification

<i>Design conditions</i>	Primary side	Secondary side
Pressure (bar abs)	130	100
Temperature (°C)	325	325
<i>Operating conditions</i>	Primary side	Secondary side
Pressure (bar abs)	1 - 116	0.023 - 80
Temperature (°C)	20 - 320	20 - T _{prim}
Mass flow (kg/s)	~2.8	~0.4
Pressure drops (kPa)	12 (at 2.8 kg/s)	30 (at 0.4 kg/s)
Primary and secondary side volume ~15 - 20 l (each side)		
Nominal power 500 kW (with ~11 plates)		
Height (m) ~ 2.70 (exchanging part)		
Width (m) ~ 0.45		
Thickness (m) ~ 0.11 (of which about 1/3 occupied by plates)		
Heat transfer surface ~13 m ²		



Commercial HX chosen

TEMPCO Model TCBC2102H*130

<i>Design conditions</i>	Primary side	Secondary side
Pressure (bar abs)	140	100
Temperature (°C)	310	310
<i>Operating conditions</i>	Primary side	Secondary side
Pressure (bar abs)	1 - 116	0.023 - 80
Temperature (°C)	20 - 310	20 - T _{prim}
Mass flow (kg/s)	~3.9 (Note 1)	~0.4
Pressure drops (kPa)	31.6 (at 3.9 kg/s)	14.4 (at 0.4 kg/s)

Primary and secondary side volume ~10 l (with 130 plates) each side

Power ~600 kW (with 130 plates)

Height (m) ~ 0.5 (exchanging part)

Width (m) ~ 0.2

Thickness (m) ~ 0.30 (with 130 plates)

Heat transfer surface ~12.16 m² (with 130 plates)

Realization with 8 nozzles (double inlet/double outlet) to have spare ones for instrumentation installation

Note 1: Primary side mass flow increase with respect to TA to have adequate PS outlet temperature higher than SS saturation temperature at 70 bar.



HX HEAT TRANSFER COEFFICIENT verification BY TEMPCO CALCULATIONS


An estimation of the heat transfer coefficients was performed on the basis of the results of TEMPCO calculations for different cases: the h_{liq} was obtained from the symmetric case and used to calculate both the h_{stm} in the superheated steam case and the h_{ss} in the base case. The $h_{stm\,cnd}$ was obtained by the h_{ss} from the base case.

	Symmetric case PS Liquid - SS Liquid	Superheated steam case PS liquid - SS Superheated steam	Base case PS Liquid - SS evaporating	Two-phase Case PS condensig - SS evaporating
Heat transfer coefficient				
Power (kW)	1402.24	6.85	602.4	606.8
DT log mean (°C)	19.915	1.477	9.276	34.20
Heat transfer area (m ²)	12.16	12.16	12.16	12.16
Plate thickness (m)	0.001	0.001	0.001	0.001
AISI 316 thermal conductivity (W/(mK))	16.2	16.2	16.2	16.2
Global heat transfer coefficient (W/(m ² K))	5790.4	381.4	5340.6	1459.1
	$\frac{1}{h_{tot}} = \frac{1}{h_{liq}} + \frac{s}{k} + \frac{1}{h_{liq}}$	$\frac{1}{h_{tot}} = \frac{1}{h_{liq}} + \frac{s}{k} + \frac{1}{h_{stm}}$	$\frac{1}{h_{tot}} = \frac{1}{h_{liq}} + \frac{s}{k} + \frac{1}{h_{ss}}$	$\frac{1}{h_{tot}} = \frac{1}{h_{stm\,cnd}} + \frac{s}{k} + \frac{1}{h_{ss}}$
	Heat transfer coefficient h_{liq} is equal both sides	Heat transfer coefficient h_{stm} obtained by h_{liq} previously calculated	Heat transfer coefficient h_{ss} obtained by h_{liq} previously calculated	Heat transfer coefficient $h_{stm\,cnd}$ obtained by h_{ss} previously calculated
h_{liq} (W/(m ² K))	18022.7			
h_{stm} (W/(m ² K)) superheated		399.2		
h_{ss} (W/(m ² K)) (evaporating)			14279.5	
$h_{stm\,cnd}$ (W/(m ² K)) (condensing)				1806.4


TEMPCO HX configuration:

- 4 nozzles for fluid (PS+SS)
- 4 nozzles for instrumentation insertion

TEMPCO HX technical sheet




Facility layout for installation on an existing load bearing structure at SIET




Piping drawings and mechanical verifications versus maximum pressure and temperature

List of main components/piping

- Steam-water separator (S-CSG bypass);
- Steam-water separator piping to and from the CSG;
- S-CSG (outer dimensions);
- In-pool heat exchanger;
- In-pool HX piping to and from the CSG;
- HX pool




MECHANICAL DESIGN Steam-Water separator (S-CSG bypass)




MECHANICAL DESIGN Primary side piping

TEMPCO PS HX inlet pipe



Drawing SIET 122.00.005 Rev.4 Sheet 2 of 7


TEMPCO PS HX outlet pipe



Drawing SIET 122.00.005 Rev.4 Sheet 1 of 7


MECHANICAL DESIGN Secondary side piping

TEMPCO SS HX inlet pipe




Drawing SIET 122.00.005 Rev.4 Sheet 3 of 7

TEMPCO SS HX outlet pipe




Drawing SIET 122.00.005 Rev.4 Sheet 4 of 7

MECHANICAL DESIGN In-pool heat exchanger



Drawing TECNIM 4422-11 Rev.04

MECHANICAL DESIGN Heat exchanger Pool



Drawing SIET 122.00.004 Rev.2

The RELAP5 code was used for the simulation of the natural circulation loop at the nominal operating conditions with the main goal of:


- verifying the size of the pipes;
- verifying the heat transfer capability of the loop.

Critical parameters in the simulation:

- Pressure drops in the piping;
- Heat transfer coefficients for both HXs;
- Filling ratio of the loop.

ELSMOR facility
RELAP5 nodalization

by ENEA







RELAP5 simulation of a transient included in the Test Matrix

Group	Test N.	PC pressure	PC temp.	PC total flow rate	PC conditions	PC HL flow rate	SC FR	SC initial temp.	Pool temp.	Pool initial level	Orifice on PC HL	SC CL valve position	SC N ₂ injection	Notes
N.	N.	bar	°C	kg/s	single/two-phase	kg/s	%	°C	°C	m	b (d/D ratio)	closing turns	NI	
4	16	120	310	23.5	1-P	3.4	30	30	30	5	1	0	0	Start-up
	17	120	320	23.5	1-P	3.4	30	TBD	30-100	5	1	0	0	Transient + steady state
	18	120	290	23.5	1-P	3.4	30	TBD	100	5	1	0	0	Tests at reduce PS temperature (power)
	19	120	260	23.5	1-P	3.4	30	TBD	100	5	1	0	0	Tests at reduce PS temperature (power)
	20	120	320	23.5	1-P	3.4	30	TBD	100	2.3	1	0	0	Test at reduced level in the Pool

Time [s]	Test - event
0-1000	Initial cold conditions, mass reduction in the SC to obtain the FR
1000-3000	Test 16: start-up with PC temperature 310°C
1050	Start PC mass flow rate
1100	Start PC temperature ramp
3000	Opening SC control valve
3000-6000	Test 17: transient+steady state with PC temperature 320°C
4000	PC temperature rise from 310°C to 320°C
6000-7000	Test 18: test at reduced PS temperature (290°C)
7000-8000	Test 19: test at reduced PS temperature (260°C)
8000-12000	Test 20: Test at reduced level in the Pool (2.3 m)
8500	Opening pool discharge valve

RELAP5 results of the simulation of a transient included in the Test Matrix



The results show that the natural circulation develops in the secondary side and no criticalities are evidenced in the design.

INSTRUMENTATION

The choice of instrumentation to be installed on a facility is made on the basis of:

- Measurement range;
- Instrument accuracy.

All the instruments must be calibrated in a calibration laboratory and calibration certificates must be checked and confirmed by qualified personnel before the installation on the loop.

Example of instrument table and needed information.


N.	Location	Instrument type	Manufact urer	Model	Plant code	SIET code	HP tap	LP tap	P1	P1 Azth.	P1 elev.	Nozzle elevatio n	P1 hsl	P1 hss	P1 hcl	P2	P2 elev.	Nozzle elevatio n	P2 hsl	P2 hss	P2 hcl	Instrum. Elevation	Head	Span	M.U.	LRV	URV	hcl net	hsl net	hss net	M	Q	K	Manufact.Error	Notes	
							(+)	(-)		(°)	(m)	(m)	(m)	(m)	(m)	(m)	(m)	(m)	(m)	(m)	(m)	(m)	(m)	Span	M.U.		M.U.	M.U.	(m)	(m)	(m)	(M.U./m V)	(M.U.)	(M.U.)	(+/- M.U.)	
1	SG Bypass (pump side) feedwater inlet mass flow	Orifice+ DP transmitter	Honeywe ll	STD830	F100 1A	18166	M18	M19	M18	n.a.	- 0.257	NA	NA	NA	1.203	M19	-0.257	NA	NA	NA	1.203	-1.460	0.000	#VALO RE!	kPa	TBD	TBD	0							0.280	
2	SG Bypass (pump side) feedwater inlet mass flow (Low Span)	Orifice+ DP transmitter	Honeywe ll	STD120	F100 1B	14722	M18	M19	M18	n.a.	- 0.257	NA	NA	NA	1.203	M19	-0.257	NA	NA	NA	1.203	-1.460	0.000	#VALO RE!	kPa	TBD	TBD	0							0.010	
3	Primary side pressurizer pressure	relative P transmitter	Honeywe ll	STG870	P100 4	22831	M24		M24	n.a.	11.72 0				9.045							2.675	9.045	13	MPa	0	13		0	0	3.24982	- 3.249 42	0.101 3	0.010		
4	Total DP across the pool (Pool Level)	DP - Transm.	Honeywe ll	STD820	DP- 001		M20	M21	M20		20.97 8				20.97 8	M21	15.59 5				15.59 5		5.383	90	kPa	-10	80	5.383								
5	IN POOL HEX TOTAL DP	DP - Transm.	Honeywe ll	STD820	DP- 002		M15	M14	M15		19.07 1				19.07 1	M14	15.75 9				15.75 9		3.312	60	kPa	-10	50	3.312								

The instruments in the ELSMOR facility are ~150.

The Data Acquisition System consists of Data acquisition boards cabled to each instrument that transmit the signals via ethernet to a PC.

The DAS boards for the ELSMOR facility are manufactured by National Instruments and the DAS program running on the PC is developed in NI-LabView ambient.

Instrument table



Data Acquisition System

The choice of DAS components and boards is made on the basis of:

- DAS board accuracy;
- Type to signal to be recorded (e.g. high level 1 - 10 V; low level ± 50 mV);
- Sampling frequency.

All the DAS boards must be calibrated in a calibration laboratory and calibration certificates must be checked and confirmed by qualified personnel before the installation and cabling.


The Data Acquisition System consists of Data acquisition boards hosted in Chasses each cabled to instruments and the signals are transmitted via ethernet to a PC.

The Chassis and board manufacture is National Instruments.


The DAS program that runs on the PC is developed in NI-LabView ambient.

It performs the raw data acquisition (Volt), the conversion to Engineering units (e.g. Pa) and to derived quantities (e.g. Kg/s).

Scheme of a DAS based on NI components



PROCESS and INSTRUMENTATION DIAGRAM



TEST MATRIX

The definition of the Test Matrix is done on the basis of:

- the phenomena to be investigated;
- the optimization of the facility operation;
- the need of specific experimental data for code validation;
- The energy cost optimization.

The Test Matrix for the ELSMOR facility consists of 62 test points grouped in 8 sections to optimize the operation.

They include tests at different filling ratios of the secondary loop and at different Primary Side temperature and flowrate conditions.

The non-condensable gas injection is also foreseen.

ELSMOR Test Matrix

Parameters to be investigated:

Primary side pressure (Primary temperature)
Pressure drop in the secondary side natural circulation loop on the cold leg and hot leg
Secondary side filling ratio
Water level in the Pool
Initial temperature in the Pool
Non-condensable gas in the secondary side
Primary side in single phase or two phase conditions

Note for testing: Start-up of the secondary side at cold conditions by establishing the specified filling ratio by removing air and water in excess by means of a vacuum pump

Grp	Test No.	PS Pressure	PS Temperature	PS total flowrate	PS conditions	PS No. flowrate	SC filling ratio	SC initial temperature	Pool level	Pool initial temperature	Pool level	SC filling ratio	SC No. flowrate	SC No. injection	Notes
1	1	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up
	2	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state
	3	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	4	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	5	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Test at reduced level in the Pool
2	6	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up
	7	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state
	8	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	9	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	10	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Test at reduced level in the Pool
3	11	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up
	12	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state
	13	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	14	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	15	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Test at reduced level in the Pool
4	16	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up
	17	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state
	18	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	19	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	20	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Test at reduced level in the Pool
5	21	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up with increased pressure drop on the SC
	22	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state with increased pressure drop on the SC
	23	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Steady state with increased pressure drop on the SC
	24	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Steady state with increased pressure drop on the SC
	25	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up with increased pressure drop on the SC
6	26	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state with increased pressure drop on the SC
	27	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Steady state with increased pressure drop on the SC
	28	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Steady state with increased pressure drop on the SC
	29	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Steady state with increased pressure drop on the SC
	30	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up with increased pressure drop on the SC
7	31	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state
	32	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	33	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	34	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Test at reduced level in the Pool
	35	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up with increased pressure drop on the SC
8	36	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state with increased pressure drop on the SC
	37	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Steady state with increased pressure drop on the SC
	38	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Steady state with increased pressure drop on the SC
	39	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Steady state with increased pressure drop on the SC
	40	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up with increased pressure drop on the SC
9	41	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state
	42	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	43	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	44	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Test at reduced level in the Pool
	45	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up with increased pressure drop on the SC
10	46	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state
	47	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	48	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	49	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Test at reduced level in the Pool
	50	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up with increased pressure drop on the SC
11	51	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state
	52	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	53	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	54	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Test at reduced level in the Pool
	55	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up with increased pressure drop on the SC
12	56	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state
	57	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	58	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	59	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Test at reduced level in the Pool
	60	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up with increased pressure drop on the SC
13	61	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state
	62	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	63	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	64	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Test at reduced level in the Pool
	65	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up with increased pressure drop on the SC
14	66	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state
	67	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	68	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	69	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Test at reduced level in the Pool
	70	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up with increased pressure drop on the SC
15	71	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state
	72	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	73	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	74	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Test at reduced level in the Pool
	75	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up with increased pressure drop on the SC
16	76	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state
	77	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	78	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	79	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Test at reduced level in the Pool
	80	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Start-up with increased pressure drop on the SC
17	81	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Transition - steady state
	82	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	83	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Tests at reduced PS temperature (given)
	84	1.00	1.00	2.5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0	Test at reduced level in the Pool

TEST EXECUTION, DATA ANALYSES AND CODE VALIDATION

The tests execution can start only after the instrument check is performed at the beginning of the testing day and it is verified all of them are within certain specified limits (Hydro-zero check).


Once experimental data are available, first a data analysis is performed to verify that the phenomena of interest are captured.

Then, data can be used for code validation with the execution of post-test analyses.

Time Schedule for ELSMOR Facility Realization and Testing

- Gantt chart

- Design review and finalization (by February 2022)
- Procurement (by May 2022)
- Test facility realization (by August 2022)
- Test facility Commissioning (by October 2022)
- Testing (by December 2022)
- Data validation and reporting (by January 2023)



■ THANK YOU!

■ ?

HEASMOOR

*Towards European Licensing of
Small Modular Reactors*

fortum

GRS
VTT

EDF

framatome

PAUL SCHERRER INSTITUT
PSI

TA
TechnicAtome

IEI

ENEA

cea

SIET
sperimentiamo le tue idee

IRSN
INSTITUT
DE RADIOPROTECTION
ET DE SÛRETÉ NUCLÉAIRE

ED
ENERGORISK

